



CentriFlow®

Material Test Report

Calcined Alumina



CentriFlow®

Date Tested:	June 2, 2000	Temperature:	Ambient (78°F/25.6°C)
Technician:	Alan Norman	Particle Size:	100 Microns
Test Location:	Eastern Instruments	Flowability:	Above Average
CFM Model:	6" Type II CentriFlow®	Cohesiveness:	None
Meter Capacity:	6.75 ft³/min	Density (lb/ft³):	65 lb/ft³
Feed System:	Screw Conveyor	Inhibit Setting:	0.200 Volts



Test #1	Percent of Volumetric Capacity = 20% - 25%				
Run #	Actual Weight	Metered Weight	Metered/Actual	Delta Weight	% Error
1	19.16	19.11	0.997	-0.050	-0.26%
2	18.16	18.14	0.999	-0.020	-0.11%
3	16.60	16.59	0.999	-0.010	-0.06%
4	18.50	18.49	0.999	-0.010	-0.05%
5	18.36	18.29	0.996	-0.070	-0.38%
Average:			0.9983		
STD:			0.0014		
% STD:			0.14%		
Additional Comments: Tested with a 6" CentriFlow® Type II Meter equipped with Vibraweigh®. The run time was 15 seconds per batch.					

Accuracy Statement:

"The CentriFlow® Meter will provide accuracy to within ±0.50% of reading when operating within ± 10% of the calibrated flow rate, as long as the flow rate is within the operational range of the meter."